

Estimate



Customer:

Jordan Taylor
Two adjoining rooms
Denver, Colorado

Cedar & Beam Builders
Illustrative project services
Denver, Colorado

Issued: 25 Sep 2026

Due: 25 Oct 2026

Scope: Install selected engineered wood flooring over a suitable prepared subfloor in two rooms, with underlay, transitions and perimeter trim.

Definition	Amount	
Perimeter trim and cleanup (job) 1.00 x \$320.00	\$320.00	
Transition profiles (each) 3.00 x \$55.00	\$165.00	
Board fitting labor (sq. ft.) 620.00 x \$6.00	\$3720.00	
Underlay allowance (sq. ft.) 620.00 x \$1.00	\$620.00	
Board material allowance (sq. ft.) 680.00 x \$7.00	\$4760.00	
Subfloor preparation (sq. ft.) 620.00 x \$2.00	\$1240.00	
Room measure and floor check (job) 1.00 x \$145.00	\$145.00	
	SubTotal	\$10970.00
	Tax 0%	\$0.00
	Total	\$10970.00

Notes:

Illustrative example; not market rates. Tax and markup not included. No subfloor reconstruction, stair treads or built-in furniture removal.

customer signature