

Estimate



Customer:

Jordan Taylor
100 linear ft. wood fence
Fredericton, NB

Cedar & Beam Builders
Fictional Canadian project services
Fredericton, NB

Issued: 25 Sep 2026

Due: 25 Oct 2026

Scope: Install 100 linear feet of wood privacy fence on an agreed accessible alignment with one gate. Example quantities include 14 posts, 300 linear feet of rails and 220 pickets. Final layout and material quantities require site verification.

Definition	Amount
Fence installation labour (linear ft.) 100.00 x C\$20.00	C\$2000.00
Concrete and hardware allowance (job) 1.00 x C\$480.00	C\$480.00
Layout and cleanup (job) 1.00 x C\$330.00	C\$330.00
Gate supply and installation (each) 1.00 x C\$430.00	C\$430.00
Posts material allowance (each) 14.00 x C\$47.00	C\$658.00
Picket material allowance (each) 220.00 x C\$3.20	C\$704.00
Rail material allowance (linear ft.) 300.00 x C\$1.85	C\$555.00
SubTotal	C\$5157.00
Tax 0%	C\$0.00
Total	C\$5157.00

Notes:

Fictional CAD prices, not market rates; tax and markup excluded. Verify your job. Excludes survey.

customer signature