

Estimate



Customer:
Jordan Taylor
100 linear ft. wood fence
Kansas City, Missouri

Cedar & Beam Builders
Illustrative project services
Kansas City, Missouri

Issued: 21 Sep 2026
Due: 21 Oct 2026
Scope: Install 100 linear feet of wood privacy fence on an agreed accessible alignment with one gate. Example quantities include 14 posts, 300 linear feet of rails and 220 pickets. Final layout and material quantities require site verification.

Definition	Amount
Gate supply and installation (each) 1.00 x \$325.00	\$325.00
Layout and cleanup (job) 1.00 x \$250.00	\$250.00
Concrete and hardware allowance (job) 1.00 x \$360.00	\$360.00
Fence installation labor (linear ft.) 100.00 x \$15.00	\$1500.00
Rail material allowance (linear ft.) 300.00 x \$1.40	\$420.00
Picket material allowance (each) 220.00 x \$2.40	\$528.00
Posts material allowance (each) 14.00 x \$35.00	\$490.00
SubTotal	\$3873.00
Tax 0%	\$0.00
Total	\$3873.00

Notes:
Illustrative example only; prices are not market rates. Tax and markup not included. No survey, old-fence removal, rock excavation, retaining structures, staining or automatic gate equipment.

customer signature