

Estimate



Customer:

Jordan Taylor
60 sq. ft. localized lap-siding repair
Toronto, ON

Cedar & Beam Builders
Fictional Canadian project services
Toronto, ON

Issued: 25 Sep 2026

Due: 25 Oct 2026

Scope: Replace 60 square feet of visibly damaged accessible lap siding on a single-storey wall after confirming suitable backing. Include removal, 72-square-foot material allowance, fitting, limited trim allowance, debris handling and cleanup. No structural or concealed moisture repair.

Definition	Amount
Access and surface protection (job) 1.00 x C\$210.00	C\$210.00
Replacement siding allowance (sq. ft.) 72.00 x C\$14.00	C\$1008.00
Damaged siding removal (sq. ft.) 60.00 x C\$5.70	C\$342.00
Limited trim and fastener allowance (job) 1.00 x C\$220.00	C\$220.00
Fitting and installation labour (sq. ft.) 60.00 x C\$19.00	C\$1140.00
Debris handling and cleanup (job) 1.00 x C\$195.00	C\$195.00
	SubTotal C\$3115.00
	Tax 0% C\$0.00
	Total C\$3115.00

Notes:

Fictional CAD prices, not market rates; tax and markup excluded. Verify your job. Excludes structural repair.

customer signature