

Estimate



Customer:
Jordan Taylor
180 linear ft. baseboard replacement
Red Deer, AB

Cedar & Beam Builders
Fictional Canadian project services
Red Deer, AB

Issued: 25 Sep 2026
Due: 25 Oct 2026
Scope: Replace 180 linear feet of baseboard in accessible rooms. Include old trim removal, a 198-linear-foot material allowance, installation, filling and caulking, and disposal. Final painting and furniture moving excluded.

Definition	Amount
Disposal and cleanup (job) 1.00 x C\$141.00	C\$141.00
Filling and caulking (linear ft.) 180.00 x C\$1.25	C\$225.00
Fasteners and consumables (job) 1.00 x C\$81.00	C\$81.00
Baseboard material allowance (linear ft.) 198.00 x C\$2.95	C\$584.10
Cutting and installation labour (linear ft.) 180.00 x C\$4.05	C\$729.00
Existing baseboard removal (linear ft.) 180.00 x C\$0.95	C\$171.00
SubTotal	C\$1931.10
Tax 0%	C\$0.00
Total	C\$1931.10

Notes:
Fictional CAD prices, not market rates; tax and markup excluded. Verify your job.
Excludes final painting.

customer signature